

BENEFICIAR: COMUNA BUDACU DE JOS  
REFACERI DRUMURI DUPA CALAMITATILE DIN 26 Iunie 2017

ANTEMASURATOARE lucrari urgente faza II

	U/M	BUDUS (1285m)			JELNA (710m)			BUDACU DE JOS (1580m)					MONARIU (600m)	SIMIONES TI1100m	TOTAL 5275m
		LA CILEAN	LA FANTA NITA	LA GORDO LA VADURI	JELNA - GHINDA I	CIMITIR TOMA	LA TOMA	DUPA CAMIN	LA TARG	ULITA 1	ULITA 2	ULITA 3			
1 = 3m															
ART DEZVIZ (L) STRADA															
LUNGIME STRADA m		250	240	580	215	110	150	380	450	200	280	270	600	1100	5275
DH02A1 Scafificarea usoara impietuire pana la 5 cm cu autogreder	100mp	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
DH04A1 Asternerea materialelor pietroase de intrtinere pietris	mc	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	142.70	142.70
TRA 01A- Transport pietris la 50 km	to	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	280.62	280.62
DH08A Curatarea platformei drumului de material adus de vifuri	mc	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
DA6B Strat de agregate naturale cilindrate cu asternere mecanica balast	mc	52.50	50.40	121.80	45.15	94.50	23.10	31.50	94.50	42.00	58.80	56.70	126.00	231.00	1107.75
TRA 01A- Transport balast la 50 km	to	110.12	105.72	255.49	94.71	0.00	48.45	66.07	198.22	88.10	123.34	118.93	0.00	0.00	2323.62
TsC 03 H1 Sapatura mecanica cu excavatorul cu comanda hidraulica	100mc					#####									0.00
P106A1 Montarea elementelor prefabricate (tub corugat D=600) inclusiv procurare tuburi	buc					0									0
TRA 01A- Transport pamant la 5 km	to					0.00									0.00

Nota: Grosimea medie a stratului de balast este de 7 cm iar a pietrisului de 5 cm

